

**Aquarion Water Company
PFAS Sampling Results**

Town/City: Newtown

Water System Name	Sample Location	Test Date	All Results Reported as parts per trillion (ppt)					TOTAL PFAS (5)	Current CT DPH Guideline	Other PFAS Tested PFBS
			PFOA	PFOS	PFHpA	PFHxS	PFNA			
Newtown Main	Newtown Wells, POE	May 2019	4	ND	2	ND	ND	6	70	ND
	Newtown Wells, POE	Jun. 2021	4	6	2	2	ND	14	70	3
	Newtown Wells, POE	Aug. 2021	5	5	3	2	ND	15	70	3
	Sandy Hook Wells #1/3/10, POE	Sep. 2019	4	ND	ND	ND	ND	4	70	ND
	Sandy Hook Wells #1/3/10, POE	Dec. 2020	2	ND	ND	ND	ND	2	70	ND
	Sandy Hook Wells #1/3/10, POE	Jun. 2021	ND	ND	ND	ND	ND	ND	70	3
	Sandy Hook Wells #7/12A/13/14, POE	Sep. 2019	5	ND	2	ND	ND	7	70	ND
	Sandy Hook Wells #7/12A/13/14, POE	Dec. 2020	3	ND	ND	ND	ND	3	70	ND
	Sandy Hook Wells #7/12A/13/14, POE	Jun. 2021	4	ND	2	ND	ND	6	70	2

Definitions:

ND - Not Detected

POE - point of entry. Sample collected after treatment as water enters the distribution system, before the first customer.